



# PT. PJ-TEK MANDIRI

TECHNICAL INSPECTION & CERTIFICATION

|                                 |                   |                                                                                     |                   |                                                                                                                                                       |
|---------------------------------|-------------------|-------------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------|
| Client                          | : PT Pertamina EP | Height of Mast                                                                      | : 96 feet         |                                                                                                                                                       |
| Rig ID                          | : RIG BW H35KD    | Hook Load                                                                           | : 97,5 Ton Metric |                                                                                                                                                       |
| Service                         | : Service Rig     | Power                                                                               | : 350 HP          |                                                                                                                                                       |
| Type                            | : Mobil Rig       | Place of Inspection                                                                 | : Yard Lapes      |                                                                                                                                                       |
| Manufacture                     | : IDECO           | Date of Inspection                                                                  | : 17 Mei 2026     |                                                                                                                                                       |
| Year                            | : 1982            | Rig Inspector                                                                       | : Yandi Handiyan  |                                                                                                                                                       |
| Model / Serial                  | : KM-96-215-GH    |                                                                                     |                   |                                                                                                                                                       |
| DAILY INSPECTION CAT III REPORT |                   |                                                                                     |                   |                                                                                                                                                       |
| No.                             | Equipment         | Deficiencies                                                                        | Categories        | Remarks / Recommendation                                                                                                                              |
| 1.                              | Rest Mast         |    | N/A               | <b>Finding</b> : N/A<br><b>MPI Result</b> : No Discontinuity<br><b>Acceptance Criteria</b> :<br>-API RP 4G Sect 6.2.3<br><b>Total Progress</b> : 100% |
| 2.                              | Leveling Jack     |   | N/A               | <b>Finding</b> : N/A<br><b>MPI Result</b> : No Discontinuity<br><b>Acceptance Criteria</b> :<br>-API RP 4G Sect 6.2.3<br><b>Total Progress</b> : 100% |
| 3.                              | Mounting Axle     |  | N/A               | <b>Finding</b> : N/A<br><b>MPI Result</b> : No Discontinuity<br><b>Acceptance Criteria</b> :<br>-API RP 4G Sect 6.2.3<br><b>Total Progress</b> : 100  |

|               |                       |                                                                                   |                     |                                                                                                                                                                                                                                                                                                                                                                                                                       |
|---------------|-----------------------|-----------------------------------------------------------------------------------|---------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <div>4.</div> | <div>Lower Mast</div> |  | <div>Critical</div> | <div><b>Finding :</b> Ditemukan 3 spot crack area lasan dan pad eyes</div> <div><b>MPI Result :</b> Discontinuity</div> <div><b>Acceptance Criteria :</b></div> <div><div>- API RP 4G Sect 6.2.3</div><div>- API RP 4G Sect 7.1</div><div>- Table 3</div></div> <div><b>Total Progress :</b> 100%</div> <div><b>Recommendation:</b> Segera lakukan perbaikan dengan mengacu standard dan prosedur yang berlaku.</div> |
|---------------|-----------------------|-----------------------------------------------------------------------------------|---------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

|    |                  |                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                            |
|----|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 5. | Base Mast        |       | <p><b>Critical</b></p> <p><b>Finding :</b> Ditemukan 2 spot crack pada lasan</p> <p><b>MPI Result :</b> Discontinuity</p> <p><b>Acceptance Criteria :</b></p> <ul style="list-style-type: none"> <li>-API RP 4G Sect 6.2.3</li> <li>-API RP 4G Sect 7.1</li> <li>-Table 3</li> </ul> <p><b>Total Progress : 100%</b></p> <p><b>Recommendation:</b> Segera lakukan perbaikan sesuai standard dan prosedur yang berlaku.</p> |
| 6. | Drilling Console |   | <p><b>Major</b></p> <p><b>Finding :</b> Ditemukan kerusakan pressure gauge 2ea</p> <p><b>MPI Result :</b> N/A</p> <p><b>Acceptance Criteria :</b></p> <ul style="list-style-type: none"> <li>-API RP 54 Sect 7.11.4</li> </ul> <p><b>Total Progress : 100%</b></p> <p><b>Recommendation:</b> Segera lakukan pergantian sesuai spesifikasi.</p>                                                                             |

## Result Finding Rig BW H35KD

| No.   | Category | Total Finding |
|-------|----------|---------------|
| 1.    | Major    | 1             |
| 2.    | Critical | 2             |
| Total |          | 3             |

Keterangan :

1. Critical :

Kerusakan dan kegagalan peralatan dan ketidaksesuaian spesifikasi yang ditentukan sehingga dapat menyebabkan kerusakan area atau nyawa manusia. Umumnya pada wilayah komponen- Komponen yang menerima beban utama proses pengeboran.

2. Major :

Kerusakan atau kegagalan peralatan akibat ketidaksesuaian spesifikasi yang ditentukan sehingga dapat merusak peralatan utama atau menghambat operasi.

Progres pekerjaan H4- 20%

Akumulatif : 55%

Dibuat oleh :

PT PJ-Tek Mandiri



Yandi Handiyan

Disetujui:

PT Pertamina EP